

PROPOSED ORGAN

FIRST UNITED METHODIST CHURCH Iowa City, Iowa

Keyaction
Stopaction

Mechanical
Electric

PEDAL ORGAN

		Pipes
16'	PRINCIPAL	32
16'	POMMER	Great
8'	OCTAVE	32
8'	FLUTE	32
4'	CHORALBASS	32
3R	RAUSCHWERK 2'	96
16'	POSAUNE	32
8'	TRUMPET	32

GREAT ORGAN

		Pipes
16'	POMMER	61
8'	PRINCIPAL	61
8'	ROHRGEDACKT	61
4'	OCTAVE	61
4'	OPENFLUTE	61
2'	SUPEROCTAVE	61
4R	MIXTURE 1-1/3'	244
8'	TRUMPET	61

SWELL ORGAN

		Pipes
8'	GAMBA	61
8'	VOIX CELESTE	56
8'	BOURDON	61
4'	PRINCIPAL	61
4'	HARMONIC FLUTE	61
2'	DOUBLETTE	61
1-1/3'	LARIGOT	61
4R	FOURNITURE	244
16'	DULZIAN	61
8'	OBOE	61
	TREMOLO	

CHOIR ORGAN

		Pipes
8'	GEMSHORN	61
8'	COPULA	61
2-2/3'	NAZARD	61
2'	BLOCKFLOTE	61
1-1/3'	TIERCE	61
3R	SCHARF 1/2'	183
8'	CROMORNE	61
	TREMOLO	

COUPLERS

GREAT TO PEDAL	Reversible by Toe Stud
SWELL TO PEDAL	Reversible by Toe Stud
CHOIR TO PEDAL	Reversible by Toe Stud
SWELL TO GREAT	
CHOIR TO GREAT	
SWELL TO CHOIR	

COMBINATIONS - By Solid State Capture System A-B Control

GENERALS	1-2-3-4-5-6	Pistons & Toe Studs
PEDAL	1-2-3-4-5-6	Toe Studs
GREAT	1-2-3-4-5-6	Pistons
SWELL	1-2-3-4-5-6	Pistons
CHOIR	1-2-3-4-5-6	Pistons

ACCESSORIES

Blower
AC/DC Rectifier
Full Organ Indicator Light
Music Rack Light
Pedalboard Light
Swell Pedal
Choir Pedal
Full Organ Reversible - Toe Stud
Organ Bench with Adjusting Crank Mechanism
Transparent Music Rack
General Cancel
Start/Stop Switch
Manual Keys - Plumwood
Sharp Keys - Palisanderwood
Stop Tablets - Cherrywood

COST

Based on an installation of early Fall 1988 the cost of the organ will be \$312,000.00. This cost to include design, construction, shipping and installation of both organ and casework.

WH/ay

10-23-86

THE HOLTKAMP ORGAN COMPANY 2909 Meyer Avenue Cleveland Ohio 44109

Established 1855

(216) 741-5180